



MAIN JIB 길이별 정격 하중표

작업 반경 (Radius)	Max.Capacity	Radius and capacity								
		M	21.0	26.0	28.0	31.0	33.0	36.0	38.0	40.0
Jib 40.0 M	2900 KG	kg	2900	2900	2800	2500	2350	2100	1850	1650
Jib 36.0 M	2900 KG	kg	2900	2900	2900	2600	2450	2200		
Jib 31.0 M	2900 KG	kg	2900	2900	2900	2750				
Jib 26.0 M	2900 KG	kg	2900	2900						

BALLAST BLOCK

MAIN JIB 길이	BALLAST BLOCK 수량		BLOCK 중량
	A - Type	B - Type	A - Type : 2.5 Ton B - Type : 2.0 Ton
40 M	1A	3B	1A + 3B = 8.5 ton
36 M	1A	2B	1A + 2B = 6.5 ton
31 M	1A	2B	1A + 2B = 6.5 ton
26 M	1A	1B	1A + 1B = 4.5 ton

***NOTE**

최대자립고(마스트10단) 설치시에는 TELES'C CAGE는 반드시 기초위치까지내려져 있어야 한다.

SCALE 1/230	ANGLE PROJECTION 3rd	DATE 2017. 07	DESIGNED BY	TITLE SY-4029 JIB CRANE
(주) 에스와이타워			DRAWN BY	DRAWING NAME 전체조립도-2
			CHECKED BY	DRAWING NO. 4029-00-02